6572509/2022/WRG/GRC-ICD01

GOVERNMENT OF ANDHRA PRADESH
ABSTRACT

Water Resources Department – Permission for Providing water supply facilities to AIIMS Campus, Mangalagiri, Guntur District from Atmakuru Storage tank as source from Guntur Channel @ 3.50 cusecs during the canal flow period – Orders - Issued.

WATER RESOURCES (WRG-GRC) DEPARTMENT

G.O.Rt.No. 2061 Dated:26.10.2022.
Read the following:-

From the Engineer-in-Chief(I), Water Resources Department, Vijayawada, Lr.No.ENC(I)/DCE-DW/OT7/AEE20/AIIMS/2022 along with enclosures, dated:11.10.2022.

@@@

ORDER:

In the reference read above, the Engineer-in-Chief (Irr), Water Resources Department, Vijayawada, has submitted his detailed report/recommendations and requested the Government to accord permission for Providing water supply facilities to AIIMS Campus, Mangalagiri from Atmakuru Storage tank as source from Guntur Channel @ 3.50 cusecs during canal flow period, subject to certain conditions.

2. Government after careful examination of the proposals of the Engineer-in-Chief (Irr), Water Resources Department, Vijayawada, hereby agreed and accord **permission for Providing water supply facilities to AIIMS Campus, Mangalagiri from Atmakuru Storage tank as source from Guntur Channel @ 3.50 cusecs during the canal flow period,** subject to the following conditions:

1. The AIIMS, Mangalagiri shall not have any right to draw water without permission of the Department.
2. The AIIMS cannot claim the permission as a right at the cost of irrigation.
3. The cost of construction of pipe line and other infrastructure should be borne by the AIIMS Mangalagiri duly acquiring the necessary land etc., at their own cost.
4. The water rates payable shall be as levied by the Government as per the norms of domestic water supply from time to time.
5. Pump house should be constructed away from the Channel bund.
6. Off take sluice should be constructed as per the norms of Water Resources Department and banks should be protected with wing walls and should be constructed with proper consolidation under the supervision of the Departmental officers.
7. The Sill level of intake pipeline should be fixed above ½ FSL of the canal.
8. Water measuring devices should be placed at the off-take point and proper locking arrangements and shuttering arrangements must be made with their own cost under the supervision of the Water Resources Department.

~2.

9. The operation of Off-Take sluice shall be under the control of Water Resources Department only.
10. The water charges are to be paid in advance for the year on Demand as per the rate fixed by the Government.
11. The AIIMS, Mangalagiri should give an undertaking that they will not raise any legal complications for not supplying water during the drought period, short fall of rains and any type of unforeseen problems.

3. The Engineer-in-Chief (Irr), Water Resources Department, Vijayawada shall take necessary action in the matter.

4. Copy of the order is available in the apegazette.cgg.gov.in website.

(BY ORDER AND IN THE NAME OF THE GOVERNOR OF ANDHRA PRADESH)

SHASHI BHUSHAN KUMAR
PRINCIPAL SECRETARY TO GOVERNMENT

To
The Engineer-in-Chief (Irr), Water Resources Department, Vijayawada.

Copy to:

The P.S to Hon'ble Minister, Water Resources Department.
The P.S to Principal Secretary to Government, Water Resources Department.
SC/SF.

//FORWARDED :: BY ORDER//

SECTION OFFICER